

UNIVERSITY OF CALCUTTA

OFFICE OF THE UNIVERSITY ENGINEER 87/1, College Street Darbhanga Building, GroundFloor Kolkata-700073 Website :-www.caluniv.ac.in

NOTICE INVITINGQUOTATION

		vites sealed tender from resourceful and bonafide contractors for the following work						
1.	N.I.T. No:	Eng /CT-216/21-22. Date: 14.12.21						
2.		REPAIRING AND PAINTING OF SEVEN NOS. ROOM (ROOM NO 1 TO 7), OFFICE ROOM, KITCHEN ROOM						
	Name of the work:	AND ONE NO. BATH ROOM AT P.G. LADY STUDENT'S HALL, 24&25, BEADON ROW. KOLKATA-700006.						
3.	Estimated Cost put to Tender:	Rs. 267545.50 (Excluding G.S.T)						
4.	Earnest Money:	A sum of 5% of the quoted amount in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is not exempted in any case.						
5.	Time of completion:	45days						
6.	Eligibility Criteria and Documents to be submitted along with Application.	Valid trade License, GST & PAN and credential for satisfactory completion of similar nature of job amounting75 % of the estimated value in a single tender in the last three financial years in Government /Government Undertaking or University of Calcutta. Original documents may be asked for verification of technical checking on the date of issuing tender paper. Failing to produce original documents, the tender will be rejected. The participant bidder must submit the following documents in sealed envelope in the tender box kept at the Office of the Engineer at the Ground Floor of the Darbhanga Building, University of Calcutta, 87/1, College Street, Kolkata – 700073 within the last date of submission of the tender. 1. NIT documents duly filled and signed by the intending bidder. 2. Bank Draft for EMD in favour of the University of Calcutta. 3. Self-attested copy of Valid trade License, GST & Pan and credentials for satisfactory completion of similar nature of jobs under Government, Government Undertaking and Universities etc. within last three years. 4. Application through postal service or courier service is not accepted.						
7.	Last date of receipt of application for tender	On 17/12/21 from 11 am to 4 pm (Must contain above mentioned. Documents. The application duly signed by Engineer CU should be enclosed with tender documents						
8.	Last date of issue of tender papers	To be downloaded from Website(www.caluniv.ac.in)						
9.	Last Date and Time of tender Submission	Dully filled and signed tender/quotation to be submitted on 21 / 12/ 2021 from 11am to 2.00 PM in to the Tender Box kept in the Office of the University Engineer The application duly signed by Engineer CU should be enclosed with tender documents						
10.	Date and Time of Tender Opening	At or after3.00 PM 21/12/2021 at the Office of the University Engineer. Intending bidders are requested to be present at the time of opening tenders/quotations						

N.I.T no : Name of work and the date of opening should be written on the sealed envelope otherwise tender will not be opened and will be rejected.

The undersigned reserves the right to reject any or all Tenders without assigning any reason what so ever.





UNIVERSITY OF CALCUTTA

Name of the work:- REPAIRING AND PAINTING OF SEVEN NOS. ROOM (ROOM NO 1 TO 7), OFFICE ROOM, KITCHEN ROOM AND ONE NO. BATH ROOM AT P.G. LADY STUDENT'S HALL, 24&25, BEADON ROW. KOLKATA-700006

N. I.T. no- Eng /CT- 216 /21-22.	Date: 14.12.2021	
Estimated cost Put to Tender:-Rs. 267545	5 <u>.50</u> (Excluding G.S.T)	
Name of Agency:-		
Address of Agency:-		
Rate quoted by Agency:- and words)	(in figure	
Signature of the Agency w	ith date &stamp:-	



UNIVERSITY OF CALCUTTA

N. I.T. no :Eng /CT-216 /21-22 Dated:14.12.2021

GENERAL TERMS AND CONDITION

- 1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial yearin sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NITwhich will be opened by the undersigned or by his representative with in the specified time and date mentioned in the NIT The tendered must write the name of the work, NIT no, the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.
- **2.** The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .
- **3**. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.
- **4.** Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maxi mumli mit of 10% of the contract value.



5. The allotted time for completion of the work as specified in the NIT from the date of receipt of work order .Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6.If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security .So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Gurrantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7. A sum of 5% of the quoted amount in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is not exempted in any case. The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder for successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs			
D.D No	Dated	/	/20
Name of Issuing Bank:			
Branch :-			

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.



- **9.**The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.
- **10.** The rates must be quoted in words in figure otherwise the tender will be cancelled.
- 11. The University will not be bound to accept the lowest bidder.
- **12**. The University will not supply any materials to the contractor.
- 13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative (Sub-Assistant- Engineer) & the contractor or his representative. The contractor will have to submit bill in printed format in duplicate.
- **14.** The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.
- 15. Defect & liability Period: The defect & liability period will be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be for feited.

Sd/-

University Engineer

Name of the Agency:

Address:-

Signature of the Agency with date &stamp:-

SPECIFIC PRICE SCHEDULE FOR REPAIRING AND PAINTING OF SEVEN NOS. ROOM (ROOM NO 1 TO 7), OFFICE ROOM, KITCHEN ROOM AND ONE NO. BATH ROOM AT P.G. LADY STUDENT'S HALL, 24&25, BEADON ROW. KOLKATA-700006.

SL.NO.	DESCRIPTION OF WORK.	NO.	QUALITY.	RATE.	AMOUNT.
				RS. P.	RS. P.
1.	Stripping off worn out plaster and				
(Page11	raking out joints of walls, ceilings				
Item10).	etc. Up to any height and in any				
	floor including removing rubbish				
	within a lead of 75m as directed.				
	2(5.0+3.5)1.8=30.6				
	2(3.7+3.5)1.8=25.92				
	2X2(6.0+3.5)1.8=68.40				
	2(3.0+3.5)1.8=23.40				
	2(6.5+3.5)1.8=36.00				
	2(3.7+2.8)1.8=23.40	C	240.00	40.00	45.00.00
	2(3.0+3.0)1.8=21.60	Sqm.	240.00	19.00	4560.00
2.	Applying 2 coats of Non-Toxic Acrylic				
(page45	Polymer modified Paint having				
Ite8b).	adhesive & waterproofing				
	properties by mixing in proportion				
	(1 liquid: 4 cementitious material) or				
	as per manufacturer's specification	Sqm.	240.00	258.00	61920.00
	for water proofing layer.	- 4			
3.	Plaster (to wall, floor, ceiling etc.)				
(page189	with sand and cement mortar				
Item1).	including rounding off or chamfering				
	corners as directed and raking out				
	joints including throating, nosing	Sqm.	240.00	195.00	46800.00
	and drip course, scaffolding/staging				
4.	where necessary. Supplying, fitting & fixing 1st quality				
	Ceramic tiles in walls and floors to				
(page64	match with the existing work & 4				
Item35).	nos. of key stones (10mm) fixed with				
	araldite at the back of each tile &				
	finishing the joints with white				
	cement mixed with colouring oxide				
	if required to match the colour of				
	tiles including roughening of				
	concrete surface, if necessary or by				
	synthetic adhesive & grout materials				
	etc.				
L		L	l .	I	

	3.0X2.0=6.0	Sqm.	6.00	746.00	4476.00
5.	Applying Interior grade Acrylic				
(page195	Primer of approved quality and				
Item7).	brand on plastered or concrete				
,	surface old or new surface to				
	receive Distemper/ Acrylic emulsion				
	paint including scraping and				
	preparing the surface throughly,				
	complete as per manufacturer's				
	specification and as per direction of				
	the EIC.				
	2(5.0+3.5)3.5=59.5				
	2(3.7+3.5)3.5=50.4 2(3.0+3.5)3.5=45.5				
	2(6.5+3.5)3.5=70.00				
	2X2(6.0+3.5)3.5=133.0				
	2(3.7+2.8)3.5=45.5				
	2(3.0+3.0)3.5=42.00				
	5X3.5=17.5				
	3.7X3.5=12.95				
	3.0X3.5=10.5				
	6.5X3.5=22.75				
	2X6X3.5=42.0				
	3.7X2.8=10.36	Sqm.	580.00	33.70	19546.00
	3X3=9				
6.	Acrylic Distemper to interior wall,				
(page196	ceiling with a coat of solvent based				
Item10).	interior grade acrylic primer (as per				
	manufacturer's specification) including cleaning and smoothning				
	of surface.	Sqm.	580.00	70.00	40600.00
7.	Supplying, fitting and fixing E.W.C. in				
(page79	white glazed vitreous chinaware of				
Item2).	approved make complete in position	Nos.	1.00	1421.00	1421.00
,	with necessary bolts, nuts etc.				
8.	upplying, fitting and fixing 10 litre				
(page36	P.V.C. low-down cistern conforming				
Item2).	to I.S. specification with P.V.C.				
	fittings complete,C.I. brackets				
	including two coats of painting to	Nos.	1.00	1015.00	1015.00
0	bracket etc.				
9.	Supplying, fitting and fixing bib cock or stop cock.				
(page6	(i) Chromium plated Bib Cock short				
Item7).	body (Equivalent to Code No. 511 &				
	Model - Tropical / Sumthing Special	Nos	<i>E</i> 00	E30.00	2224.00
	of ESSCO or similar brand).	Nos.	6.00	539.00	3234.00
10.	Painting with best quality synthetic				
(page200	enamel paint of approved make and				
Item1+2).	brand including smoothening				
,	surface by sand papering etc.				
	Including using of approved putty				
	etc. On the surface, with a coat of				

					,
	primer.				
	Skirting-2(5+3.5)0.2=3.4				
	2(3.7+3.5)0.2=2.88				
	2(3+3.5)0.2=2.6				
	2(6.5+3.5)0.2=4.0				
	2x5(6.0+3.5)0.2=19				
	2(3.7+2.8)0.2=2.6				
	2(3+3)0.2=2.4				
	Barga-100x3.5x.1=35				
	17x3x0.1=5.1				
	Beam-3x5x0.8=112				
	2x3.7x0.8=5.92				
	2x3.5x0.8=5.6				
	4x6.5x2x0.8=41.6				
	2x2x3.7x0.8=11.84				
	Pan door-10x1.0x2.0x2.6=52	Sqm.	310.00	117.00	36270.00
11.	Supplying, fitting and fixing boiling				
(page173	water proof ply conforming to IS:				
Item2).	710-1977 bonded with phenol				
	formaldehyde synthetic resin				
	conforming to IS: 848-1974 of				
	approved make and brand fitted and				
	fixed as per design as per approval				
	and direction of Engineer-in-Charge.				
	[excluding the cost of supporting				
	frame work and teak wood				
	batten/Lipping].				
	4 mm thick.	Sqm.	10.00	923.00	9230.00
12.	Supplying fitting, fixing decorative				
(page179	lamination conforming to IS: 2046 :				
Item14).	1995 as per approved make, brand,				
,	finish and thickness with fitting,				
	fixing the same on Particle/MDF /				
	Ply Boards with recommended /				
	approved adhesive with proper				
	clipping the sides for better				
	attachment as per direction of				
	Engineer-incharge.The rate includes				
	the cost of labour, adhesive and all				
	incidental charges thereof.	Sqm.	10.00	802.00	8020.00
	1.5mm thick.	'			
13.	Removal of rubbish,earth etc. from				
(page12	the working site and disposal of the				
Item13).	same beyond the compound, in				
1.011113).	conformity with the Municipal /				
	Corporation Rules for such disposal,				
	loading into truck and cleaning the				
	site in all respect as per direction of				
	Engineer in charge.	Sqm.	15.00	166.00	2490.00
14.	Wood work in door and window				
(Page114	frame fitted and fixed in position				
Item1).	complete including a protective coat				
itemii,	of painting at the contact surface of				
L		1			

the frame excluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected up to three decimals). Sal-Malayasian.	Cum.	0.25	83218.00	20804.50 770.00
Cleaning sitt of inspection pit	INUS.	3.00	154.00	770.00
Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per				
sq. Cm. 20mm 15mm.	Nos. Nos.	1.00 1.00	604.00 438.00	604.00 438.00
Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007. with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials.				
40mm 20 mm	Rmt. Rmt.	4.00 15.00 15.00	403.00 143.00 106.00	1612.00 2145.00 1590.00
	concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected up to three decimals). Sal-Malayasian. Cleaning silt of inspection pit Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. Cm. 20mm 15mm. Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007 . with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. 40mm	concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected up to three decimals). Sal-Malayasian. Cleaning silt of inspection pit Cum. Cleaning silt of inspection pit Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. Cm. 20mm 15mm. Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007 . with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. 40mm accesories, specials. 40mm Accesories, specials. Rmt. Rmt.	concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected up to three decimals). Sal-Malayasian. Cum. Cleaning silt of inspection pit Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. Cm. 20mm 15mm. Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007 . with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. 40mm 20 mm Rmt. 4.00 Rmt. 15.00	concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected up to three decimals). Sal-Malayasian. Cleaning silt of inspection pit Cleaning silt of inspection pit Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. Cm. 20mm 15mm. Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007 . with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. 40mm 20 mm Rmt. 4.00 403.00 403.00 143.00

TOTAL
ESTIMATED
COST-----

------RS.267545.50

Name of the Agency

Address of the Agency

Rate quoted by the Agency

Signature of the Agency with date